

MINUTES OF THE COMMITTEE CONSTITUTED FOR REVIEW AND RECOMMENDATIONS OF QUOTATIONS FOR NON-SOR ITEMS HELD ON DT. 06-08-2026 @ 5.00PM AT APCRDA OFFICE, RAYAPUDI, AMARAVATHI

Sub: APCRDA — "WORLD BANK & ADB financed Amaravati Capital City Development Program related to 'Completion of balance works viz., Architectural Finishes, Internal & External Electrical, Plumbing & Sanitary Fixtures, Fire Fighting Provisions, Lifts, DG, HVAC, Security Systems, External Development & Landscaping etc., for Multi Storied Quarters of 432 Apartment units in 18 towers of (S+12) Floors Pattern Buildings for Hon'ble MLAs & Hon'ble MLCs and All India Services Officers near Nelapadu, Amaravati, Andhra Pradesh' on Lumpsum Contract (% Percentage Tender) System with DLP of 2 Years" — **Agenda: Committee constituted for approval supplementary Non-SoR items Rates — Approved — Reg.**

Reference Citations:

- APCRDA 38th Authority Meeting, Resolution No.467/2024 Dt. 16-10-2024
- Administrative Sanction: G.O.RT.No. 676 of Municipal Administration & Urban Development (CRDA) Department, Dt: 13-07-2025 for Rs.524.70 Crores.
- Technical Sanction Vide No. 06/CE/ Project Office/2024-25, Dt. 30-12-2024 for Rs 524.70 Cr.
- Chief Engineer (H&B), APCRDA, Agreement No.04/MLA&MLC/H&B Housing/2025-26, Dt: 28-04-2025.
- G.O. RT. No. 792 of Municipal Administration & Urban Development (CRDA) Department, Dt: 12-08-2025.
- Approved Agenda of Committee-III vide MAU61-OPCS0AGNC(AGMT)/1/2024-HB-Part (1) dated 24.03.2026 of the Commissioner, APCRDA, Amaravati.
- Supplementary agreement 36/CE(H&B-H)/MLA&MLC Housing/supple-2/ H&B Housing /2025-26 Dt: 30.03.2026.
- Rc.No. MAU61-USI/4/2026/Deviations, Date: 31-07-2026.

Committee Members:

- Sri. R.G. Krishna Reddy**, Group Director (ENC), APCRDA — *Chairman*
- Sri. P.V.K. Bhaskar**, Chief Engineer, APCRDA — *Convenor*
- Sri B. Narasimha Murthy**, Chief Engineer, ADCL — *Member*
- Sri Ch. Dhanunjaya**, Chief Engineer, ADCL — *Member*
- Sri. M.V. Rao**, Chief Engineer, APCRDA — *Member*
- Sri. G Sudhakar Reddy**, Chief Engineer, AGICL — *Member*
- Sri.P. Muralidhar**, Chief Engineer-PMU, APCRDA — *Member*
- Sri. K.S. Chatterji**, Contract manager Expert, Pg Mc — *Member*
- Sri Harshavardhan**, CE, Electrical, AGICL — *Member*
- Chief Engineer**, APCRDA (Concerned) — *Convenor*

Complete Schedule of 24 Approved Non-SoR Items

S.No	Item Code & Description	Unit	Qty	Adopted Rate (₹)	Amount (₹)	Technical Remarks & Justification
1	Mild Steel Shaft Door: Providing and fixing powder coated mild steel shaft door with frame and shutter fabricated from skin-pass galvanized iron sheets conforming to IS:513 (D Quality) and galvanized as per IS:277 (120 g/sqm). Frame 1.20mm GI sheet with PUF insulation, shutter 0.80mm GI sheet (46mm thick flush double skin) with honeycomb kraft core infill, 60-65 microns powder coating, 6mm float vision glass, SS butt hinges, mortise sash lock.	Sqm	442	10,957.00	48,45,843.00	Rate not in SoR. Adopted rate based on market quotations and lower than prevailing market rate. Approved for APCRDA Project office work.
2	Basketball Goal Post Set: Complete Basketball Goal Post Set conforming to FIBA standards, heavy duty MS pipe/box section pole (3-5mm thickness), base plate (12mm), synthetic enamel/powder coated.	No	3	80,250.00	2,40,750.00	3 quotations obtained. Rayzon Global LLP quotation lowest and most economical. Conforms to FIBA standards.
3	Rubberized Flooring: Providing and laying rubberized flooring Base coat 34mm, Top Layer 6mm over podium slab top conforming to IS 809:1992	Sqm	2,900	5,191.00	1,50,52,448.00	Executed for Kids' Play Area and Walking Track over podium slabs at MLA, MLC & AIS Towers. Rate lower than market rate.

S.No	Item Code & Description	Unit	Qty	Adopted Rate (₹)	Amount (₹)	Technical Remarks & Justification
	and IS 1197:1970 with surface preparation and adhesives.					
4	Toilet False Ceiling: Gyp Board Fine Line Grid false ceiling for Toilets (PVC Laminated GS-FLC-4.6) 600x600mm / 595x595mm tiles conforming to IS 2095-1982 with GI precoated grid and suspension rods.	Sqm	11,215	1,218.00	1,36,60,105.00	Required to prevent maintenance issues and achieve moisture-resistant architectural finish in high-rise toilets.
5	Expansion Joint (Top Horizontal): Supply and Installation of BIZZAR 446 050 with grooved Flexible High Quality Elastomeric Inserts (-30°C to +120°C, UV stabilized, wheel load 30kN car/300kN lorry DIN 1991, 200mm joint size with 5mm movement).	Rmt	1,236	5,500.00	67,95,965.00	Proposed as deviation/supplementary item based on actual site joint movement and weather requirements.
6	Expansion Joint (Bottom Horizontal): Supply and installation of BIZZAR 23W-050 extruded aluminum base with Snap-in Tension Clip System for Horizontal Ceiling to Ceiling Flat application (25mm to 75mm width).	Rmt	1,236	4,500.00	55,60,335.00	Derived from competitive market quotations; lowest and technically justified.
7	Expansion Joint (Vertical Internal): BIZZAR 23W-050 aluminum profiles with tension clip system for Vertical Wall to Wall Flat application (25mm to 75mm joint width).	Rmt	500	3,470.00	17,35,000.00	Required for internal vertical expansion transitions between adjacent tower blocks.
8	Expansion Joint (Vertical External): Wall to Wall external expansion joint with 50mm hook-shaped aluminum clip, 6063 alloy clear anodized matt finish, gasket seals, and watertight moisture barrier membrane.	Rmt	500	4,590.00	22,95,000.00	Watertight requirement for external tower facade expansion gaps.
9	Active Leakage Treatment (PU Grouting): Single component Polyurethane Foam injection grout (10:1 resin:accelerator, expansion >30x) + Two-component PU resin (2:1 base:hardener, adhesion >2.5 MPa, elongation >80%, ASTM D 2196) with non-return packers.	Nos	14,400	1,800.00	2,59,20,000.00	SoR 2025-26 rate is ₹2,259.80 with CP. Adopted 20% less than total cost and rounded off to ₹1,800.00 per nozzle.
10	Grass Lawn on Podium: Providing and laying grass lawn/grass turf with approved Doob grass including 75mm good earth dressing, compacting, planting, watering and 30-day maintenance.	Sqm	3,373	550.00	18,55,228.00	Executed on podium tops as part of approved landscaping and beautification works.
11	Concrete Saucer Drain: Cement concrete saucer drain in CC 1:2:4 including excavation, dressing, laying slope, and smooth finish with cement mortar 1:2.	Rmt	1,100	1,100.00	12,10,000.00	Rate approved in Project Office and PEB Sheds works. Constructing saucer drain along cement concrete roads.
12	HVAC IDU Servicing & Painting: HVAC Indoor Unit cover removing, internal coil and casing cleaning, cover painting, and refixing package including material and manpower.	No	450	4,200.00	18,90,000.00	Restored deteriorated indoor units exposed during construction hiatus to operational status on-site.
13	CI Y-Strainer 200mm Dia: Supply, installation, testing and commissioning of 200mm dia Cast Iron Y-strainer.	No	9	60,542.00	5,44,878.00	Fire Protection: Integrated into 200mm fire main headers to prevent clogging of deluge valves and sprinklers.
14	CI Y-Strainer 100mm Dia: Supply, installation, testing and commissioning of 100mm dia Cast Iron Y-strainer.	No	9	15,798.00	1,42,182.00	Fire Protection: Integrated into 100mm fire lines.
15	Diesel Engine Main Fire Pump (2280 LPM @ 120m Head): Multistage centrifugal pump of CI body & bronze impeller, SS shaft, 1500 RPM water-cooled diesel engine (Kirkloskar/Cummins), 12V/24V auto starter, diesel tank, 50mm glass wool insulation with 1mm aluminum cladding, red paint, base plate & anti-vibration pads.	No	4	5,26,995.00	21,07,980.00	Rate derived based on market quotations from authorized manufacturers. Comprehensive retrofitting and 2-year warranty included.
16	Electric Main Fire Hydrant Pump (2850 LPM @ 88m Head): Horizontal centrifugal pump, 415V 3-phase 50Hz, CI casing, CS diffusers, bronze impeller, SS 304 shaft, 2900 RPM TEFC IP55 motor (Class F	No	2	7,15,413.00	14,30,826.00	Derived from authorized manufacturer market quotations. 2 years warranty.

S.No	Item Code & Description	Unit	Qty	Adopted Rate (₹)	Amount (₹)	Technical Remarks & Justification
	insulation conforming to IS 325-1978), cushy foot mountings, epoxy base frame.					
17	Jockey Pressurization Pump (180 LPM @ 120m Head): Vertical centrifugal pump, CI casing, SS shaft, bronze impeller with mechanical seal, 415V 3-phase TEFC 2900 RPM motor.	No	2	1,48,945.00	2,97,890.00	Pressurization maintenance pump for fire lines. 2 years warranty.
18	RCC Core Cutting (up to 100mm dia, thickness up to 200mm): Diamond core cutting in RCC walls, slabs, beams, columns for dia 50-100mm including cutting rebar, scaffolding, and disposal.	Each	8,766	568.00	49,79,088.00	Required for sanitary, electrical and drainage pipe penetrations not provided in original RCC cast.
19	RCC Core Cutting (150mm to 250mm dia, thickness up to 200mm): Diamond core cutting in RCC members for dia 150-250mm for large ducts and sleeve penetrations.	Each	11,142	807.00	89,91,594.00	Required for HVAC ducts, electrical cables, and large drainage sleeves.
20	RCC Core Cutting (75mm to 150mm dia, heavy thickness 275mm to 500mm): Diamond core cutting in heavy transfer slabs and podium slabs of thickness 275mm to 500mm.	Each	6,600	1,376.00	90,81,600.00	Core cutting through heavy podium transfer slabs.
21	Passenger Elevator Retrofitting (Batch 1 - 10 Units): Thyssenkrupp Electric Traction Lift, 15 Passenger/1020Kg, G+12 Floors (13 Stops/13 Landings), 1.5-1.75 mps, MRL, COPO/TOPO doors (1000/1100x2100mm), SS COP with Braille, scrolling LED, bilingual VAS (Telugu & English), intercom, 2.0MP FHD CCTV, ARD with SMF VRLA batteries, Fireman switch, PMSM gearless machine, VVVF regenerative closed loop drive.	No	10	34,61,452.00	3,46,14,520.00	Net approved rate ₹34,61,452/lift after deducting installed usable parts (₹5.80 Lakhs: guide rails ₹80k, door frames ₹3L, doors ₹2L) from gross ₹40,41,452. Saves ~₹20 Lakhs/lift compared to new lift (₹55-56 Lakhs). 3-year warranty + CAMC.
22	Passenger Elevator Retrofitting (Batch 2 - 10 Units): Same specification as Sl.No. 21 (10 additional Thyssenkrupp lift units across towers).	No	10	34,61,452.00	3,46,14,520.00	Same justification and net rate ₹34,61,452 per unit.
23	RCC Concrete Repair & Hole Filling (up to 100mm dia): Repairing and filling holes, voids, tie rod holes, and minor honeycombs with SBR/epoxy bonding agent and polymer modified cement mortar 1:3.	Nos	16,878	250.00	42,19,500.00	Structural patch repair and finishing. Quantity supplemented based on actual tie-rod hole counts.
24	RCC Concrete Repair & Hole Filling (up to 200mm dia): Repairing and filling holes, voids, and honeycomb patches up to 200mm dia with SBR/epoxy bonding agent and polymer modified mortar 1:3.	Nos	9,666	350.00	33,83,100.00	Structural patch repair. Rate lower than market rates.
TOTAL	GRAND TOTAL (24 APPROVED NON-SOR ITEMS)				₹18,83,36,712.00	₹18.83 Crores Sanctioned & Approved

Official Committee Resolution:

"Hence, it is **RESOLVED THAT** the above-mentioned 24 Non-SOR items have been duly scrutinized and reviewed by comparing the quotations received with the prevailing market rates through a detailed market rate analysis. Upon such verification, it has been observed that the rates quoted and adopted are lower than the prevailing market rates and are found to be reasonable and justified. Accordingly, the Committee hereby recommended the rates of the said Non-SOR items."

Signed by Chairman, Convenor, and Committee Members on 06-08-2026 at APCRDA Office, Rayapudi, Amaravathi.